



Ministry of Education  
Department of Construction  
Architect and Engineering Section

Bill of Quantity for bore well in Depth of ( ) meter including all services

No.	Items		Unit	Quantity	Unit Cost(USD)	Total Cost of one Well	Remarks
1	Drilling of wells diameter 8" - 10"	کنندگاری چاه به قطر (8 - 10) انچ	Meter				
2	Filter & Pipe lowering	انداختن پمپ و فلتر	LMP	1			
3	Back filling ( Soil and Gravel ) include providing gravel	انداختن خاک و جفل	LMP	1			
4	Installation of Hand pump	نصب پمپ دستی	Set	1			
5	Indus hand pump long pedestal including all rubber and plastic parts complete set	تجهه ست مکمل پمپ دستی	Set	1			
6	PVC Rising main 2" diameter	پمپ پلاستیکی 2 انچ پمپ دستی	Meter				
7	PVC ( Class - B ) 4" diameter pipe	پمپ پلاستیکی 4 انچ	Meter				
8	PVC ( Class - B ) 4" dia Filter pipe	پمپ پلاستیکی 4 انچ فلتر	Meter				
9	Plate form ( Apron )	کاتگوریت اطراف چاه (پران)	LMP	1			
10	Gravel for gravel packing	جفل جهت پرکاری اطراف پمپ و فلتر	M <sup>3</sup>				
11	Rod for hand pump	راد پمپ دستی	Meter				
	<b>Total</b>						

کنندگاری چاه طوری باید صورت گیرد حداقل به ارتفاع 20 متر آب در چاه موجود باشد. و برآورده دیزاین چاه از طرف شرکت ساختمانی نظر به موقعیت مکتب صورت گرفته و قیمت داده میشود .

نوت -

